

Sec. 16-11-82. Pre-installation testing. Storage

Every water meter shall be tested as required by these regulations prior to its installation either by the manufacturer, the utility or any commission approved laboratory equipped for meter testing. Meters with oil-enclosed gear trains should be stored in an inverted position and, if not so stored, shall be tested immediately before installation.

(Effective October 18, 1966)